


BONDING DETAILS									
Bar Work	Qty	Size	Total Length	Type	X'	Y'	Z'	T'	V'
SDR	120	#3	8'-2 1/2"	TL	0'-4 1/2"	3'-4"	0'-7"	3'-2"	0'-4 1/2"
SDR	160	#3	6'-1 1/2"	TL	0'-4 1/2"	2'-1 1/2"	0'-7"	2'-1 1/2"	0'-7"
4706	64	#4	4'-0"	17	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"
4711	64	#4	4'-9"	17	2'-9"	2'-9"	2'-9"	2'-9"	2'-9"
5705	2	#5	5'-10"	20	2'-0"	1'-3 1/2"	2'-6 1/2"	2'-0"	2'-0"
5707	80	#5	6'-0"	3	2'-4"	3'-8"	2'-4"	2'-1 1/2"	2'-6 1/2"



STRUCTURAL NOTES	
LEGENDS	LABEL LEGENDS
T - TOP V, VERT - VERTICAL H, HORIZ - HORIZONTAL CLR - CLEAR COVER SIM - SIMILAR TYP. - TYPICAL T.O.MAT - TOP OF MAT E5 - EACH SIDE EF - EACH FACE CONT - CONTINUOUS COR - CORNER THK. - THICKNESS ADDL. - ADDITIONAL DIAG. - DIAGONAL NTS - NOT TO SCALE CEN. - CENTER LINE SDR - STRUCTURAL DRAWING REFERENCE	6x2x6 #4 40#12' B2 NOTES BAR MARK BAR SIZE NUMBER OF BARS EACH FACE/EACH SIDE NUMBER OF LOCATIONS DENOTES OPENINGS DENOTES KNOCK OUTS
WALL PANEL	CLEAR COVER TO REINFORCEMENT
2"	AT ENDS
1 1/2"	#5 & BELOW AT EXTERIOR FACE
2"	#6 & ABOVE AT EXTERIOR FACE
3/4"	AT INTERIOR FACE

7	
6	
5	
4	
3	
2	06.10.2019
1	05.24.2019

NORTH WALL PANELS PLACING DRAWING REFERENCE	
DWG.NO:	DRAWING DESCRIPTION
R-4	NORTH WALL PANELS N-1 TO N-8
R-5	NORTH WALL PANELS N-9 TO N-15
R-6	NORTH WALL PANELS N-16 TO N-22
R-7	NORTH WALL PANELS N-23 TO N-29
R-8	NORTH WALL PANELS N-30 TO N-36
R-9	NORTH WALL PANELS N-31 TO N-43
R-10	NORTH WALL PANELS N-44 TO N-50
R-II	NORTH WALL PANELS N-51 TO N-58
R-I2	NORTH WALL PANELS N-59 TO N-66
R-13	NORTH WALL PANELS N-67 TO N73
R-14	NORTH WALL PANELS N-74 TO N-81

REINFORCING STEEL PLACING DRAWING ONLY. USE IN CONJUNCTION WITH CONTRACT DRAWINGS & SPECIFICATIONS. ELEVATIONS & DIMENSIONS SHOWN ON THIS DRAWING ARE FOR DETAILING PURPOSES ONLY AND SHOULD NOT BE USED FOR CONSTRUCTION UNLESS VERIFIED BY ENGINEER OR CONTRACTOR.

7	
6	
5	
4	
3	
2	06.10.2019
1	05.24.2019
RE SUBMITTED FOR APPROVAL	
DATE	
APPROVAL SENT FOR	
RE-STEEL SUPPLY CO., INC.	
REINFORCING STEEL - WIRE MESH	
200 Eddystone Industrial Park • Eddystone, PA 19022-1588	
Phone: 800-876-8216 • Fax: 610-876-8428	
Structure	VALLEY VIEW BUSINESS PARK TILT PANELS
Location	JESSUP, PA
Architect	KSS ARCHITECTS
Engineer	RICHARD ADAMS
Customer	T&T CONSTRUCTION
Made by:	Date:
PRO	05.24.2019
CONTRACT NO. U2524	
DRAWING COVERS	
NORTH WALL PANELS N-74 TO N-81	
REV. NO.	DATE
DESCRIPTION	
DRAWING NO. R-14	